

# Commissioning and First Operation of the Low-beta and their Electrical Feed-Boxes at the Large Hadron Collider (LHC)


C. Darve<sup>1</sup>, C. Balle<sup>2</sup>, J. Casas-Cubillos<sup>2</sup>, S. Claudet<sup>2</sup>, S. Feher<sup>1</sup>, G. Ferlin<sup>2</sup>, J. Kerby<sup>1</sup>, L. Metral<sup>2</sup>, A. Perin<sup>2</sup>, T. Peterson<sup>1</sup>, H. Prin<sup>2</sup>, R. Rabehl<sup>1</sup>, N. Vauthier<sup>2</sup>, U. Wagner<sup>2</sup>, R. van Weelden<sup>2</sup>

<sup>1</sup>Fermi National Accelerator Laboratory  
Batavia, IL, 60510, USA

<sup>2</sup>European Organization for Nuclear Research  
Geneva, 1211, Switzerland

**CEC-ICMC**


**June 28 - July 2, 2009  
Tucson, Arizona, USA**




- **The LHC Low- $\beta$  Magnet System Descriptions**
  - Low- $\beta$  magnets – Inner Triplets
  - Electrical Feed-boxes – DFBX
  - LHC Low- $\beta$  Magnet System Operation
  
- **Hardware Commissioning**
  - Selected Key Issues
  - First Operation
  
- **Low- $\beta$  Magnet Systems History**
  
- **Concluding Comments**



# The LHC Low- $\beta$ Magnet Systems



Squeeze the beam size down at the collision point to increase the chances of a collision






CEC - July 1st 2009

25 Jun 2009




# The LHC Low- $\beta$ Magnet System




The low- $\beta$  magnet systems are composed of :


- One electrical feed box (DFBX)
- Four 70 mm aperture quadrupole magnets (Q1, Q2a, Q2b, Q3) so-called the inner triplet
- One beam separation dipole magnet (D1), superconducting at the low luminosity IPs
- Five corrector magnet assemblies



# Low- $\beta$ Magnet – Inner Triplets





The low- $\beta$  triplets are Nb-Ti superconductor quadrupole magnets, which operate at 215 T/m in superfluid helium at a temperature of 1.9 K.



38,490 m  
CEC - July 1st 2009




# Electrical Feed-boxes - DFBX






# DFBX – 7.5 kA - HTS current Leads




7.5 kA current leads power the main inner triplet quadrupoles


- Lead tested at full current at FNAL
- Power cables installed @ surface
- Operated similarly to CERN HTS leads – Control @ 50 K, Interlocks
- Each lead cooling uses a RT temperature sensor, a flag heater operated with local thermo-couple



Silicone High Voltage Insulator Coating




# DFBX - Vapor Cooled Leads - Resistive Leads



- 600 A (14/DFBX) and 120 A (10/DFBX) power the corrector magnets
- Current lead was tested at full current at manufacturer (AMI)
- Power cables installed @ surface
- Each 600 A lead and pair of 120 A leads is cooled by the boil-off from the helium tank.
  - No temperature sensors on the leads cold end, only at the flag heater.
  - Manufacturer has specified a mass flow rate per lead.
- Helium gas is warmed up before being recovered to the warm recovery line – Interlocks
- Each lead cooling uses a temperature sensor, a flag heater operated with local thermo-couple




AMI 600 A 6 Lead Assembly Test Data  
Voltage Drop vs. Coolant Flow






# LHC Low- $\beta$ Magnet System First Operation



- Preparation to cool-down (e.g. pressure test, flushing)  
Cool-down time : 15 → less than 4 days



- Preparation to powering (e.g. valve & instrumentation check, electrical quality assurance to verify the integrity of the each electrical circuits)

Powering magnet phases : > 2 weeks








# DFBX VCL Parameters Tuning during Powering




## Determination of the current lead ramp rates





# DFBX Vapor Cooled Lead - Control System





**Issue:** No temperature sensors on lead cold-end and no reliable flow measurement (virtual flow measurement, no hardware installed).

**Solution:** Installed new instrumentation, flexible Pt100.




Very difficult access to permit the electrical feed-boxes consolidation with high risk of damage to delicate wiring

## DFLY.3R2.1-6 (1chimney\*6leads - 600A)






## DFBX VCL - Water Condensation Issue



**Issue:** Following the first DFBX cool-downs, water and ice ball observed on the VCL room temperature VL chimney interface.


**Solution:** Installed bracket heaters on the VCL chimneys and around each lead.



Local heater used to warm up helium gas to room temperature before it is collected in the WRL.



New Pt100 used to regulate the vapor cooled lead flow – Process variable of the controlled valve to the WRL circuit.


New bracket heater used to prevent condensation to appear around the vapor cooled lead chimneys and used to maintain a known temperature distribution along the helium flow path.



**Issue:** Offset observed on the measured temperature of the 600 A VCL (electronic background noise caused by the electronics floating with respect to the ground).

**Solution:** Implemented a 4.7  $\mu\text{F}$  capacitor per temperature channel. Twelve capacitors are grouped in one so-called filter-box, which is directly plugged-in the instrumentation connector of the DFBX.





**Issue:** Passive heaters were systematically mis-installed, generating extra static heat load for half of the inner triplets and risking liquid fill of the counter-flow heat exchanger for the other half

**Solution:** Re-installed two of these eight passive heaters (high luminosity points)

Cutting cryostat, shield and MLI




Installing passive heaters



Installing temperature sensors



New temperature sensors




Re-installed 2 braids






# Inner Triplet – Chamonix Workshop – J. Strait




- Bus splices are inside thin-walled (0.25 mm) bellows  
→ vulnerable to puncture/rupture in case of an electrical arc
- Old cryostat relief system is three 67 mm ports => capacity of 1~1.5 kg/s
- Rupture of interconnect M-line (stored energy 6.5 MJ vs. one main ARC dipole 7.5 MJ):
  - Substantially enhance relief capacity, e.g. adding several DN200 to each triplet.
- Bus fault rupturing interconnect bellows:
  - Up to 20 kg/s helium flow into cryostat, pressurized to many bar.
  - Anchors to floor will break for  $P > 1.5\sim 2$  bar.
  - DFBX (square cryostat) could be severely damaged by internal pressure.  
No spare DFBX\* => 1-2 years to build new from scratch.
- Inter-turn short puncturing/rupturing cold bore tube.
  - Scaling from a similar incident with an SSC R&D magnet, such an event could create a 20-30 mm diameter hole in the beam tube.
  - Up to 10 kg/s high pressure helium released into vacuum tube, adjacent to experiments, in presence of electrical arc.




CEC - July 1st 2009



# Low- $\beta$ Magnet System History



- Design and development
- Production
- Delivery at CERN
- First triplet assembly
- First triplet in tunnel (8L)
- Pressure test (8L)
- Repair of HX in all triplets
- First cool-down of low-b
- Hard. Commissioning- ph1
- First powering (5L)
- Consolidations of DFBX
- First operation
- Consolidation of IT
- Hard. Commissioning- ph2




→ 180 W load from secondaries Only for IT in the high luminosity areas could there be some runs, in between the collimation phase-2 and ATLAS/CMS phase-1 period at  $10^{34}$  cm<sup>-2</sup>.sec<sup>-1</sup>

→ 60 W prior to this phase.



# Concluding Comments



The first operation of the low-beta and their electrical feed-boxes was finally successful !

- Key issues were identified to permit the proper LHC operation
  - Staged consolidations were necessary
  - Complex and difficult access for repair require high reliability of components
- 
- Lessons learned for future designs with emphasize on:
    - ✓ Risk Analysis
    - ✓ Structural Safety
    - ✓ Engineering Safety Documentation

Safety code used : ASME Pressure Vessel Code / CERN Safety Code D2 Rev 2